Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
119	123.8		Cum	1	4.80	2.30	0.23	2.54		
		7th Cross road								
		Left side								
36	41.4		Cum	1	5.40	2.40	0.23	2.98		
		Right side								
162	167.5		Cum	1	5.50	2.40	0.23	3.04		
		6th cross road								
		Left side								
44	49.2		Cum	1	5.20	2.30	0.23	2.75		
		Right side					0.23	0.23		
96	101.3		Cum	1	5.30	2.30	0.23	2.80		
		CQAL layout								
		20th C cross								
		Left side								
32	37.2		Cum	1	5.20	2.00	0.23	2.39		
		Right side					0.23			
83	88.5		Cum	1	5.50	2.00	0.23	2.53		
		1st A main								
		Right side								
28	33.2		Cum	1	5.20	2.00	0.23	2.39		
		1st B Main					0.23			
		Left side								
31	36.4		Cum	1	5.40	2.00	0.23	2.48		
		3rd main, C block								
		Left side								
12	17.2		Cum	1	5.20	2.00	0.23	2.39		
		6th main								
		Right side								
56	61.5		Cum	1	5.50	2.00	0.23	2.53		
101	106.2		Cum	1	5.20	2.00	0.23	2.39		
		5th main								
74	79.2		Cum	1	5.20	2.00	0.23	2.39		
		20th D cross								
		Left side								
15	20.5		Cum	1	5.50	1.20	0.23	1.52		
96	101.3		Cum	1	5.30	1.20	0.23	1.46		
		CQAL Layout								
		5th Cross Road								
		Left side								
0	15		Cum	1	15.00	0.90	0.23	3.11		
15	30		Cum	1	15.00	0.90	0.23	3.11		
30	45		Cum	1	15.00	0.90	0.23	3.11		
45	60		Cum	1	15.00	0.90	0.23	3.11		
60	75		Cum	1	15.00	0.90	0.23	3.11		
75	90		Cum	1	15.00	0.90	0.23	3.11		
90	105		Cum	1	15.00	0.90	0.23	3.11		
105	120		Cum	1	15.00	0.90	0.23	3.11		
120	135		Cum	1	15.00	0.90	0.23	3.11		
135	150		Cum	1	15.00	0.90	0.23	3.11		
150	163		Cum	1	13.00	0.90	0.23	2.69		
		Right side								
0	15		Cum	1	15.00	0.80	0.23	2.76		
15	30		Cum	1	15.00	0.80	0.23	2.76		
30	45		Cum	1	15.00	0.80	0.23	2.76		
45	60		Cum	1	15.00	0.80	0.23	2.76		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
		Culvert to kodigehalli Circle	Cum	1	50.50	16.80	0.60	509.04		
		Culvert to Underpass	Cum	1	138.30	16.10	0.65	1447.31		
								Total Qty	**2277.65**	
								Tender Qty	**600.60**	
								Qty upto 125%	**750.75**	**342.53**	**257154.40**
								Above 125%	**1526.90**	**342.53**	**523008.89**
		Basic rate	302							
		6% weightage	18.12							
		Total Rs.	320.12							
		(+7%)TP	22.408							
		Net Total Rs.	**342.53**							
Item no.11		Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechaniqal mix plant carriage ' of mixed Material by tipper to site, laying in uniform layers with paver in sub- base/ base course on well prepared surface and compacting with vibratory roller to achieve the desired density.complete as per specifications.and as per the directions of the Engineer-in-charge of the work .								
		Defencce layout								
		1st Cross road								
		Left side								
59	64.2		Cum	1	5.20	2.40	0.23	2.87		
		Right side								
91	96.5		Cum	1	5.50	2.40	0.23	3.04		
		2nd cross road								
		Left side								
18	23.5		Cum	1	5.50	2.40	0.23	3.04		
87	92.3		Cum	1	5.30	2.40	0.23	2.93		
		Right side								
113	118.7		Cum	1	5.70	2.40	0.23	3.15		
		3rd cross road								
		Left side								
25	30.6		Cum	1	5.60	2.40	0.23	3.09		
		Right side								
78	83.8		Cum	1	5.80	2.40	0.23	3.20		
128	133.2		Cum	1	5.20	2.40	0.23	2.87		
		7th main Road								
		Left side								
0	15		Cum	1	15.00	2.20	0.23	7.59		
15	30		Cum	1	15.00	2.20	0.23	7.59		
30	45		Cum	1	15.00	2.20	0.23	7.59		
45	60		Cum	1	15.00	2.20	0.23	7.59		
60	75		Cum	1	15.00	2.20	0.23	7.59		
75	90		Cum	1	15.00	2.20	0.23	7.59		
90	105		Cum	1	15.00	2.20	0.23	7.59		
105	120		Cum	1	15.00	2.20	0.23	7.59		
120	138		Cum	1	18.00	2.20	0.23	9.11		
		Right side								
0	15		Cum	1	15.00	1.40	0.23	4.83		
15	30		Cum	1	15.00	1.30	0.23	4.49		
30	45		Cum	1	15.00	1.20	0.23	4.14		
45	60		Cum	1	15.00	1.20	0.23	4.14		
60	75		Cum	1	15.00	2.20	0.23	7.59		
75	90		Cum	1	15.00	2.20	0.23	7.59		
90	105		Cum	1	15.00	2.20	0.23	7.59		
105	120		Cum	1	15.00	2.20	0.23	7.59		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
		3rd main road								
		Left side								
51	56.2		Cum	1	5.20	2.30	0.23	2.75		
81	86.2		Cum	1	5.20	2.30	0.23	2.75		
		Right side								
119	123.8		Cum	1	4.80	2.30	0.23	2.54		
		7th Cross road								
		Left side								
36	41.4		Cum	1	5.40	2.40	0.23	2.98		
		Right side								
162	167.5		Cum	1	5.50	2.40	0.23	3.04		
		6th cross road								
		Left side								
44	49.2		Cum	1	5.20	2.30	0.23	2.75		
		Right side					0.23	0.23		
96	101.3		Cum	1	5.30	2.30	0.23	2.80		
		CQAL layout								
		20th C cross								
		Left side								
32	37.2		Cum	1	5.20	2.00	0.23	2.39		
		Right side					0.23			
83	88.5		Cum	1	5.50	2.00	0.23	2.53		
		1st A main								
		Right side								
28	33.2		Cum	1	5.20	2.00	0.23	2.39		
		1st B Main					0.23			
		Left side								
31	36.4		Cum	1	5.40	2.00	0.23	2.48		
		3rd main, C block								
		Left side								
12	17.2		Cum	1	5.20	2.00	0.23	2.39		
		6th main								
		Right side								
56	61.5		Cum	1	5.50	2.00	0.23	2.53		
101	106.2		Cum	1	5.20	2.00	0.23	2.39		
		5th main								
74	79.2		Cum	1	5.20	2.00	0.23	2.39		
		20th D cross								
		Left side								
15	20.5		Cum	1	5.50	1.20	0.23	1.52		
96	101.3		Cum	1	5.30	1.20	0.23	1.46		
		CQAL Layout								
		5th Cross Road								
		Left side								
0	15		Cum	1	15.00	0.90	0.23	3.11		
15	30		Cum	1	15.00	0.90	0.23	3.11		
30	45		Cum	1	15.00	0.90	0.23	3.11		
45	60		Cum	1	15.00	0.90	0.23	3.11		
60	75		Cum	1	15.00	0.90	0.23	3.11		
75	90		Cum	1	15.00	0.90	0.23	3.11		
90	105		Cum	1	15.00	0.90	0.23	3.11		
105	120		Cum	1	15.00	0.90	0.23	3.11		
120	135		Cum	1	15.00	0.90	0.23	3.11		
135	150		Cum	1	15.00	0.90	0.23	3.11		
150	163		Cum	1	13.00	0.90	0.23	2.69		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
		Right side								
0	15		Cum	1	15.00	0.80	0.23	2.76		
15	30		Cum	1	15.00	0.80	0.23	2.76		
30	45		Cum	1	15.00	0.80	0.23	2.76		
45	60		Cum	1	15.00	0.80	0.23	2.76		
60	75		Cum	1	15.00	0.80	0.23	2.76		
75	90		Cum	1	15.00	0.80	0.23	2.76		
90	105		Cum	1	15.00	0.80	0.23	2.76		
150	166		Cum	1	16.00	0.80	0.23	2.94		
		Maruthinagar								
		5th A cross road								
0	15.5		Cum	1	15.50	4.60	0.23	16.40		
		5th B cross								
0	20		Cum	1	20.00	4.60	0.23	21.16		
		5th D cross								
0	15		Cum	1	15.00	5.50	0.23	18.98		
15	25.5		Cum	1	10.50	5.60	0.23	13.52		
		9thB Cross Bhadrappa Layout								
0	15		Cum	1	15.00	6.00	0.23	20.70		
18	28		Cum	1	10.00	3.00	0.23	6.90		
30	42		Cum	1	12.00	4.65	0.23	12.85		
49	59		Cum	1	10.00	3.30	0.23	7.59		
63	75		Cum	1	12.00	5.20	0.23	14.35		
77	85		Cum	1	8.00	2.83	0.23	5.20		
88	101.1		Cum	1	13.10	4.95	0.23	14.93		
106	114		Cum	1	8.00	2.86	0.23	5.25		
		11th Cross Maruthi nagar Layout								
0	15		Cum	1	15.00	2.20	0.23	7.59		
15	30		Cum	1	15.00	5.25	0.23	18.11		
32	43		Cum	1	11.00	3.00	0.23	7.59		
49	60		Cum	1	11.00	3.00	0.23	7.59		
62	71		Cum	1	9.00	3.20	0.23	6.62		
		3rd cross Devinagar								
0	15		Cum	1	15.00	3.70	0.23	12.77		
16	25		Cum	1	9.00	2.00	0.23	4.14		
27	42		Cum	1	15.00	3.40	0.23	11.73		
44	54		Cum	1	10.00	2.20	0.23	5.06		
56	75		Cum	1	19.00	3.50	0.23	15.30		
78	90		Cum	1	12.00	2.20	0.23	6.07		
93	107		Cum	1	14.00	3.80	0.23	12.24		
		Hanumaiah Layout Main Road								
		Left side								
13	17.1		Cum	1	4.10	2.00	0.23	1.89		
56	59.2		Cum	1	3.20	2.00	0.23	1.47		
156	160.4		Cum	1	4.40	2.00	0.23	2.02		
258	262.3		Cum	1	4.30	2.00	0.23	1.98		
348	352.1		Cum	1	4.10	2.00	0.23	1.89		
418	422.2		Cum	1	4.20	2.00	0.23	1.93		
		Right side								

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
		Left side								
0	15		Cum	1	15.00	1.00	0.23	3.45		
15	30		Cum	1	15.00	0.90	0.23	3.11		
30	45		Cum	1	15.00	0.85	0.23	2.93		
45	55		Cum	1	10.00	0.85	0.23	1.96		
60	65.2		Cum	1	5.20	0.90	0.23	1.08		
70	75.2		Cum	1	5.20	0.90	0.23	1.08		
		3rd B cross								
0	15		Cum	1	15.00	4.75	0.23	16.39		
15	28		Cum	1	13.00	4.85	0.23	14.50		
		3rd B cross opposite road								
0	15		Cum	1	15.00	4.40	0.23	15.18		
15	26		Cum	1	11.00	4.35	0.23	11.01		
		3rd C cross road								
0	15		Cum	1	15.00	4.05	0.23	13.97		
15	24		Cum	1	9.00	4.15	0.23	8.59		
		3rd D cross road								
0	4		Cum	1	4.00	4.95	0.23	4.55		
4.7	10		Cum	1	5.30	4.95	0.23	6.03		
20	25.3		Cum	1	5.30	4.95	0.23	6.03		
35	39		Cum	1	4.00	4.95	0.23	4.55		
		UAS appartment								
0	30		Cum	1	30.00	4.50	0.23	31.05		
		1st cross (from dead end)								
0	29		Cum	1	29.00	4.65	0.23	31.02		
		2nd Cross								
0	18.5		Cum	1	18.50	4.50	0.23	19.15		
		3rd Cross								
0	17.8		Cum	1	17.80	4.00	0.23	16.38		
		4th Cross								
0	32.7		Cum	1	32.70	4.80	0.23	36.10		
		5th Cross								
0	16.5		Cum	1	16.50	3.90	0.23	14.80		
16.5	25.2		Cum	1	8.70	2.65	0.23	5.30		
		6th Cross								
0	32.1		Cum	1	32.10	4.30	0.23	31.75		
		GURUDARSHAN LAYOUT								
		7th A cross								
0	4		Cum	1	4.00	5.00	0.23	4.60		
		7th main road								
0	22		Cum	1	22.00	4.80	0.23	24.29		
		JNANESHWARI LAYOUT								
		1St Cross Road								
0	30		Cum	1	30.00	4.70	0.23	32.43		
30	58.1		Cum	1	28.10	5.10	0.23	32.96		
		2nd Cross Road								
0	30		Cum	1	30.00	4.70	0.23	32.43		
30	65.2		Cum	1	35.20	4.70	0.23	38.05		
		3rd Cross Road								
0	30		Cum	1	30.00	5.40	0.23	37.26		
30	67.6		Cum	1	37.60	4.75	0.23	41.08		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
		SIR M.V LAYOUT								
		2nd main road(ganesh temple road or gas godown)								
		Left side								
0	30		Cum	1	30.00	0.60	0.23	4.14		
30	60		Cum	1	30.00	0.60	0.23	4.14		
60	90		Cum	1	30.00	0.60	0.23	4.14		
90	120		Cum	1	30.00	0.60	0.23	4.14		
120	150		Cum	1	30.00	0.60	0.23	4.14		
150	180		Cum	1	30.00	0.60	0.23	4.14		
180	210		Cum	1	30.00	0.60	0.23	4.14		
210	240		Cum	1	30.00	0.60	0.23	4.14		
		Right side								
0	30		Cum	1	30.00	0.40	0.23	2.76		
30	60		Cum	1	30.00	0.40	0.23	2.76		
60	90		Cum	1	30.00	0.40	0.23	2.76		
90	120		Cum	1	30.00	0.40	0.23	2.76		
120	150		Cum	1	30.00	0.40	0.23	2.76		
150	180		Cum	1	30.00	0.40	0.23	2.76		
180	210		Cum	1	30.00	0.40	0.23	2.76		
210	240		Cum	1	30.00	0.40	0.23	2.76		
		10th cross								
0	26		Cum	1	26.00	0.70	0.23	4.19		
26	52		Cum	1	26.00	3.00	0.23	17.94		
		cross road								
5	9		Cum	1	4.00	4.95	0.23	4.55		
		cross road								
0	10		Cum	1	10.00	4.50	0.23	10.35		
		Kempegowda nagara main road								
0	15		Cum	1	15.00	5.55	0.23	19.15		
15	30		Cum	1	15.00	5.55	0.23	19.15		
30	45		Cum	1	15.00	5.50	0.23	18.98		
45	60		Cum	1	15.00	5.45	0.23	18.80		
60	75		Cum	1	15.00	5.40	0.23	18.63		
75	90		Cum	1	15.00	5.50	0.23	18.98		
90	105		Cum	1	15.00	5.25	0.23	18.11		
105	120		Cum	1	15.00	5.20	0.23	17.94		
120	135		Cum	1	15.00	5.80	0.23	20.01		
135	150		Cum	1	15.00	5.85	0.23	20.18		
150	171		Cum	1	21.00	5.90	0.23	28.50		
171	186		Cum	1	15.00	6.20	0.23	21.39		
		1st cross road Kempegowda nagara								
0	15		Cum	1	15.00	6.10	0.23	21.05		
15	40		Cum	1	25.00	5.75	0.23	33.06		
		Tennis court road								
0	15		Cum	1	15.00	5.95	0.23	20.53		
15	30		Cum	1	15.00	5.45	0.23	18.80		
30	45		Cum	1	15.00	5.45	0.23	18.80		
45	60		Cum	1	15.00	5.40	0.23	18.63		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
195	210		Cum	1	15.00	0.4	0.23	1.38		
210	225		Cum	1	15.00	0.4	0.23	1.38		
225	240		Cum	1	15.00	0.4	0.23	1.38		
240	245.2		Cum	1	5.20	0.4	0.23	0.48		
		Right Side								
0	15		Cum	1	15.00	0.45	0.23	1.55		
15	30		Cum	1	15.00	0.45	0.23	1.55		
30	45		Cum	1	15.00	0.45	0.23	1.55		
45	60		Cum	1	15.00	0.45	0.23	1.55		
60	75		Cum	1	15.00	0.45	0.23	1.55		
75	90		Cum	1	15.00	0.45	0.23	1.55		
90	105		Cum	1	15.00	0.45	0.23	1.55		
105	120		Cum	1	15.00	0.45	0.23	1.55		
120	135		Cum	1	15.00	0.45	0.23	1.55		
135	150		Cum	1	15.00	0.45	0.23	1.55		
150	165		Cum	1	15.00	0.45	0.23	1.55		
165	180		Cum	1	15.00	0.45	0.23	1.55		
180	195		Cum	1	15.00	0.45	0.23	1.55		
195	210		Cum	1	15.00	0.45	0.23	1.55		
210	225		Cum	1	15.00	0.45	0.23	1.55		
225	240		Cum	1	15.00	0.45	0.23	1.55		
240	245.2		Cum	1	5.20	0.45	0.23	0.54		
		2nd Block 3rd Cross Road								
		Left Side								
0	15		Cum	1	15.00	0.6	0.23	2.07		
15	30		Cum	1	15.00	0.6	0.23	2.07		
30	45		Cum	1	15.00	0.6	0.23	2.07		
45	60		Cum	1	15.00	0.6	0.23	2.07		
60	75		Cum	1	15.00	0.6	0.23	2.07		
75	90		Cum	1	15.00	0.6	0.23	2.07		
90	105		Cum	1	15.00	0.6	0.23	2.07		
105	134.5		Cum	1	29.50	0.6	0.23	4.07		
		Right Side								
0	15		Cum	1	15.00	0.5	0.23	1.73		
15	30		Cum	1	15.00	0.5	0.23	1.73		
30	45		Cum	1	15.00	0.5	0.23	1.73		
45	60		Cum	1	15.00	0.5	0.23	1.73		
60	75		Cum	1	15.00	0.5	0.23	1.73		
75	90		Cum	1	15.00	0.5	0.23	1.73		
90	105		Cum	1	15.00	0.5	0.23	1.73		
105	134.5		Cum	1	29.50	0.5	0.23	3.39		
		2nd Block 5th Cross Road								
		Left Side								
0	15		Cum	1	15.00	0.55	0.23	1.90		
15	30		Cum	1	15.00	0.55	0.23	1.90		
30	45		Cum	1	15.00	0.55	0.23	1.90		
45	60		Cum	1	15.00	0.55	0.23	1.90		
60	75		Cum	1	15.00	0.55	0.23	1.90		
75	90		Cum	1	15.00	0.55	0.23	1.90		
90	105		Cum	1	15.00	0.55	0.23	1.90		
105	120		Cum	1	15.00	0.55	0.23	1.90		
120	135		Cum	1	15.00	0.55	0.23	1.90		
135	150		Cum	1	15.00	0.55	0.23	1.90		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
150	165		Cum	1	15.00	0.55	0.23	1.90		
165	180		Cum	1	15.00	0.55	0.23	1.90		
		Right Side								
0	15		Cum	1	15.00	0.55	0.23	1.90		
15	30		Cum	1	15.00	0.55	0.23	1.90		
30	45		Cum	1	15.00	0.55	0.23	1.90		
45	60		Cum	1	15.00	0.55	0.23	1.90		
60	75		Cum	1	15.00	0.55	0.23	1.90		
75	90		Cum	1	15.00	0.55	0.23	1.90		
90	105		Cum	1	15.00	0.55	0.23	1.90		
105	120		Cum	1	15.00	0.55	0.23	1.90		
120	135		Cum	1	15.00	0.55	0.23	1.90		
135	150		Cum	1	15.00	0.55	0.23	1.90		
150	165		Cum	1	15.00	0.55	0.23	1.90		
165	180		Cum	1	15.00	0.55	0.23	1.90		
		3rd Block 7th Cross Road								
		Left Side								
0	15		Cum	1	15.00	0.6	0.23	2.07		
15	30		Cum	1	15.00	0.6	0.23	2.07		
30	45		Cum	1	15.00	0.6	0.23	2.07		
45	60		Cum	1	15.00	0.6	0.23	2.07		
60	75		Cum	1	15.00	0.6	0.23	2.07		
75	90		Cum	1	15.00	0.6	0.23	2.07		
90	105		Cum	1	15.00	0.6	0.23	2.07		
105	120		Cum	1	15.00	0.6	0.23	2.07		
120	135		Cum	1	15.00	0.6	0.23	2.07		
135	150		Cum	1	15.00	0.6	0.23	2.07		
150	165		Cum	1	15.00	0.6	0.23	2.07		
165	180		Cum	1	15.00	0.6	0.23	2.07		
180	192.6		Cum	1	12.60	0.6	0.23	1.74		
		Right Side								
0	15		Cum	1	15.00	0.55	0.23	1.90		
15	30		Cum	1	15.00	0.55	0.23	1.90		
30	45		Cum	1	15.00	0.55	0.23	1.90		
45	60		Cum	1	15.00	0.55	0.23	1.90		
60	75		Cum	1	15.00	0.55	0.23	1.90		
75	90		Cum	1	15.00	0.55	0.23	1.90		
90	105		Cum	1	15.00	0.55	0.23	1.90		
105	120		Cum	1	15.00	0.55	0.23	1.90		
120	135		Cum	1	15.00	0.55	0.23	1.90		
135	150		Cum	1	15.00	0.55	0.23	1.90		
150	165		Cum	1	15.00	0.55	0.23	1.90		
165	180		Cum	1	15.00	0.55	0.23	1.90		
180	192.6		Cum	1	12.60	0.55	0.23	1.59		
		3rd Block 8th Cross Road								
		Left Side								
0	15		Cum	1	15.00	0.55	0.23	1.90		
15	30		Cum	1	15.00	0.55	0.23	1.90		
30	45		Cum	1	15.00	0.55	0.23	1.90		
45	60		Cum	1	15.00	0.55	0.23	1.90		
60	75		Cum	1	15.00	0.55	0.23	1.90		
75	90		Cum	1	15.00	0.55	0.23	1.90		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
75	90		sqm	1	15.00	3.85		57.75		
90	105		sqm	1	15.00	3.85		57.75		
105	121		sqm	1	16.00	4.60		73.60		
120	136.3		Sqm	1	16.30	4.30		70.09		
		Sidlingeshwara layout, Thindlu								
0	15		sqm	1	15.00	4.70		70.50		
15	30		sqm	1	15.00	4.85		72.75		
30	45		sqm	1	15.00	4.55		68.25		
45	60		sqm	1	15.00	4.20		63.00		
60	75		sqm	1	15.00	4.25		63.75		
75	90		sqm	1	15.00	4.05		60.75		
90	105		sqm	1	15.00	3.90		58.50		
105	120		sqm	1	15.00	3.90		58.50		
120	135		sqm	1	15.00	3.95		59.25		
135	155		sqm	1	20.00	4.05		81.00		
		Gowdru Beedi thindlu								
0	15		sqm	1	15.00	4.90		73.50		
15	30		sqm	1	15.00	4.55		68.25		
30	45		sqm	1	15.00	4.75		71.25		
45	62		sqm	1	17.00	7.15		121.55		
		BASAVA SAMITHI LAYOUT								
		3'B cross								
0	30		Sqm	1	30.00	5.00		150.00		
30	60		Sqm	1	30.00	4.85		145.50		
60	90		Sqm	1	30.00	4.75		142.50		
90	126		Sqm	1	36.00	4.65		167.40		
		Opposite to 3rd B cross								
0	30		Sqm	1	30.00	5.60		168.00		
30	42.7		Sqm	1	12.70	5.40		68.58		
		3rd C cross road								
0	44.9		Sqm	1	44.90	5.00		224.50		
		Opposite to 3rd C cross								
0	30		Sqm	1	30.00	5.50		165.00		
30	60		Sqm	1	30.00	4.35		130.50		
60	90		Sqm	1	30.00	4.25		127.50		
90	120		Sqm	1	30.00	4.50		135.00		
120	136.3		Sqm	1	16.30	4.30		70.09		
		Kempegowda nagara main road								
0	15		sqm	1	15.00	5.55		83.25		
15	30		sqm	1	15.00	5.55		83.25		
30	45		sqm	1	15.00	5.50		82.50		
45	60		sqm	1	15.00	5.45		81.75		
60	75		sqm	1	15.00	5.40		81.00		
75	90		sqm	1	15.00	5.50		82.50		
90	105		sqm	1	15.00	5.25		78.75		
105	120		sqm	1	15.00	5.20		78.00		
120	135		sqm	1	15.00	5.80		87.00		
135	150		sqm	1	15.00	5.85		87.75		
150	171		sqm	1	21.00	5.90		123.90		
171	186		sqm	1	15.00	6.20		93.00		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
		3rd cross								
0	30		Sqm	1	30.00	1.80		54.00		
30	60		Sqm	1	30.00	1.90		57.00		
60	90		Sqm	1	30.00	1.75		52.50		
90	120		Sqm	1	30.00	3.85		115.50		
120	150		Sqm	1	30.00	3.53		105.90		
150	180		Sqm	1	30.00	3.35		100.50		
180	213		Sqm	1	33.10	1.75		57.93		
		4th cross								
0	30		Sqm	1	30.00	1.80		54.00		
30	60		Sqm	1	30.00	1.90		57.00		
60	90		Sqm	1	30.00	1.75		52.50		
90	120		Sqm	1	30.00	3.85		115.50		
120	150		Sqm	1	30.00	3.53		105.90		
150	180		Sqm	1	30.00	3.35		100.50		
180	210		Sqm	1	30.00	1.75		52.50		
210	225		Sqm	1	15.00	1.80		27.00		
		SIR M.V LAYOUT								
		2nd main 6th cross road								
		left side								
22	26		Sqm	1	4.00	0.70		2.80		
78	80.5		Sqm	1	2.50	0.85		2.13		
103	105		Sqm	1	1.50	0.65		0.98		
		Right side								
110	112		Sqm	1	1.50	0.90		1.35		
154	155.2		Sqm	1	1.20	0.65		0.78		
197	198.2		Sqm	1	1.20	0.70		0.84		
		2nd main 7'A cross road								
		left side								
36	39.5		Sqm	1	3.50	0.90		3.15		
77	86		Sqm	1	9.00	0.85		7.65		
101	103		Sqm	1	2.40	0.75		1.80		
		Right side								
0	36		Sqm	1	36.00	0.65		23.40		
45	48.7		Sqm	1	3.70	0.75		2.78		
67	70		Sqm	1	3.00	0.80		2.40		
197	199.4		Sqm	1	2.40	0.85		2.04		
		BK Layout								
		2nd cross road								
0	15		sqm	1	15.00	4.65		69.75		
15	30		sqm	1	15.00	4.70		70.50		
30	45		sqm	1	15.00	4.40		66.00		
45	60		sqm	1	15.00	4.15		62.25		
60	75		sqm	1	15.00	4.25		63.75		
75	90		sqm	1	15.00	3.85		57.75		
90	105		sqm	1	15.00	3.85		57.75		
105	121		sqm	1	16.00	4.60		73.60		
120	136		Sqm	1	16.30	4.30		70.09		
		1st Main road								
0	15		Sqm	1	15.00	4.30		64.50		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
0	44.9		Sqm	1	44.90	5		224.50		
		Opposite to 3rd C cross								
0	30		Sqm	1	30.00	5.50		165.00		
30	60		Sqm	1	30.00	4.35		130.50		
60	90		Sqm	1	30.00	4.25		127.50		
90	120		Sqm	1	30.00	4.50		135.00		
120	136		Sqm	1	16.30	4.30		70.09		
		UAS appartment								
0	30		Sqm	1	30.00	4.50		135.00		
		3rd D cross road								
0	4		Sqm	1	4.00	5.00		20.00		
4.7	10		Sqm	1	5.30	4.95		26.24		
20	25.3		Sqm	1	5.30	4.95		26.24		
35	39		Sqm	1	4.00	4.95		19.80		
		3'A cross								
10	15.3		Sqm	1	5.30	0.9		4.77		
24.7	30		Sqm	1	5.30	0.9		4.77		
		JNANESHWARI LAYOUT								
		1St Cross Road								
0	30		Sqm	1	30.00	4.70		141.00		
30	58.1		Sqm	1	28.10	5.10		143.31		
		2nd Cross Road								
0	30		Sqm	1	30.00	4.70		141.00		
30	65.2		Sqm	1	35.20	4.70		165.44		
		3rd Cross Road								
0	30		Sqm	1	30.00	4.95		148.50		
30	67.6		Sqm	1	37.60	4.70		176.72		
		Kempegowda nagara main road								
0	15		sqm	1	15.00	5.55		83.25		
15	30		sqm	1	15.00	5.55		83.25		
30	45		sqm	1	15.00	5.50		82.50		
45	60		sqm	1	15.00	5.45		81.75		
60	75		sqm	1	15.00	5.40		81.00		
75	90		sqm	1	15.00	5.50		82.50		
90	105		sqm	1	15.00	5.25		78.75		
105	120		sqm	1	15.00	5.20		78.00		
120	135		sqm	1	15.00	5.80		87.00		
135	150		sqm	1	15.00	5.85		87.75		
150	171		sqm	1	21.00	5.90		123.90		
171	186		sqm	1	15.00	6.20		93.00		
		1st cross road Kempegowda nagara								
0	15		sqm	1	15.00	6.10		91.50		
15	40		sqm	1	25.00	5.75		143.75		
		Tennis court road								
0	15		sqm	1	15.00	5.95		89.25		
15	30		sqm	1	15.00	5.45		81.75		
30	45		sqm	1	15.00	5.45		81.75		
45	60		sqm	1	15.00	5.40		81.00		
60	75		sqm	1	15.00	5.40		81.00		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
		Right side								
91	96.5		Sqm	1	5.50	2.40		13.20		
		2nd cross road								
		Left side								
18	23.5		Sqm	1	5.50	2.40		13.20		
87	92.3		Sqm	1	5.30	2.40		12.72		
		Right side								
113	118.7		Sqm	1	5.70	2.40		13.68		
		3rd cross road								
		Left side								
25	30.6		Sqm	1	5.60	2.40		13.44		
		Right side								
78	83.8		Sqm	1	5.80	2.40		13.92		
128	133.2		Sqm	1	5.20	2.40		12.48		
		7th main Road								
		Left side								
0	15		Sqm	1	15.00	2.20		33.00		
15	30		Sqm	1	15.00	2.20		33.00		
30	45		Sqm	1	15.00	2.20		33.00		
45	60		Sqm	1	15.00	2.20		33.00		
60	75		Sqm	1	15.00	2.20		33.00		
75	90		Sqm	1	15.00	2.20		33.00		
90	105		Sqm	1	15.00	2.20		33.00		
105	120		Sqm	1	15.00	2.20		33.00		
120	138		Sqm	1	18.00	2.20		39.60		
		Right side								
0	15		Sqm	1	15.00	1.40		21.00		
15	30		Sqm	1	15.00	1.30		19.50		
30	45		Sqm	1	15.00	1.20		18.00		
45	60		Sqm	1	15.00	1.20		18.00		
60	75		Sqm	1	15.00	2.20		33.00		
75	90		Sqm	1	15.00	2.20		33.00		
90	105		Sqm	1	15.00	2.20		33.00		
105	120		Sqm	1	15.00	2.20		33.00		
		3rd main road								
		Left side								
51	56.2		Sqm	1	5.20	2.30		11.96		
81	86.2		Sqm	1	5.20	2.30		11.96		
		Right side								
119	123.8		Sqm	1	4.80	2.30		11.04		
		7th Cross road								
		Left side								
36	41.4		Sqm	1	5.40	2.40		12.96		
		Right side								
162	167.5		Sqm	1	5.50	2.40		13.20		
		6th cross road								
		Left side								
44	49.2		Sqm	1	5.20	2.30		11.96		
		Right side						0.00		
96	101.3		Sqm	1	5.30	2.30		12.19		
		CQAL layout								
		20th C cross								
		Left side								
32	37.2		Sqm	1	5.20	2.00		10.40		
		Right side								

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
0	15		Sqm	1	15.00	4.65		69.75		
15	30		Sqm	1	15.00	3.80		57.00		
30	45		Sqm	1	15.00	3.10		46.50		
45	60		Sqm	1	15.00	3.30		49.50		
60	75		Sqm	1	15.00	3.70		55.50		
75	85		Sqm	1	10.00	4.10		41.00		
		Near Under Pass (Pot hole)								
0	13		Sqm	1	13.00	5.20		67.60		
13	22		Sqm	1	9.00	5.00		45.00		
28	39		Sqm	1	11.00	3.30		36.30		
47	52		Sqm	1	5.00	4.50		22.50		
77	86		Sqm	1	9.00	2.00		18.00		
		1st main								
		Left side								
82	88		Sqm	1	6.00	2.00		12.00		
115	120		Sqm	1	5.00	2.20		11.00		
		1st A main								
		Left side								
47	53		Sqm	1	6.00	2.00		12.00		
56	62.3		Sqm	1	6.30	1.60		10.08		
97	101		Sqm	1	4.00	2.00		8.00		
		Right side								
128	135		Sqm	1	7.00	2.00		14.00		
		Dr Rajgopal road kodigehalli								
		Culvert to kodigehalli Circle	Sqm	1	50.50	16.80		848.40		
		Culvert to Underpass	Sqm	1	138.30	16.10		2226.63		
		Tata Nagar								
		5th Cross	Sqm	1	205.00	1.60		328.00		
		3rd main Road	Cum	1	76.00	2.20		167.20		
		Infront Of Little wonder								
0	15		Sqm	1	15.00	6.50		97.50		
15	30		Sqm	1	15.00	6.40		96.00		
30	45		Sqm	1	15.00	6.40		96.00		
45	60		Sqm	1	15.00	6.60		99.00		
60	65		Sqm	1	5.00	6.60		33.00		
		Beside little wonder School								
0	15		Sqm	1	15.00	6.00		90.00		
15	30		Sqm	1	15.00	6.10		91.50		
30	45		Sqm	1	15.00	6.40		96.00		
45	50		Sqm	1	5.00	6.70		33.50		
		1st cross road								
0	15		Sqm	1	15.00	6.70		100.50		
15	30		Sqm	1	15.00	6.30		94.50		
30	45		Sqm	1	15.00	6.30		94.50		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
45	60		Sqm	1	15.00	6.60		99.00		
60	72		Sqm	1	12.00	6.60		79.20		
		5th cross road								
		Left side								
15	28		Sqm	1	13.00	2.30		29.90		
73	79		Sqm	1	6.00	2.30		13.80		
		Right side								
98	106		Sqm	1	8.00	2.30		18.40		
122	130		Sqm	1	8.00	2.30		18.40		
		Amco layout 1st main(impact college opp)								
0	19		Sqm	1	19.00	8.00		152.00		
32	40.3		Sqm	1	8.30	4.00		33.20		
49	59		Sqm	1	10.00	6.50		65.00		
64	69		Sqm	1	5.00	2.60		13.00		
75	88		Sqm	1	13.00	6.60		85.80		
92	106		Sqm	1	14.00	4.00		56.00		
91	103		Sqm	1	11.60	7.00		81.20		
109	113		Sqm	1	4.00	2.80		11.20		
118	129		Sqm	1	11.00	7.00		77.00		
133	146		Sqm	1	13.00	5.00		65.00		
		VIRUPAKSHAPURA								
		1st cross (pole factory road)								
		left side								
0	30		Sqm	1	30.00	0.60		18.00		
30	60		Sqm	1	30.00	0.60		18.00		
60	90		Sqm	1	30.00	0.60		18.00		
90	120		Sqm	1	30.00	0.60		18.00		
120	150		Sqm	1	30.00	0.60		18.00		
150	180		Sqm	1	30.00	0.60		18.00		
180	210		Sqm	1	30.00	0.60		18.00		
210	228		Sqm	1	18.00	0.60		10.80		
		Right side								
0	30		Sqm	1	30.00	0.55		16.50		
30	60		Sqm	1	30.00	0.55		16.50		
60	90		Sqm	1	30.00	0.55		16.50		
90	120		Sqm	1	30.00	0.55		16.50		
120	150		Sqm	1	30.00	0.55		16.50		
150	180		Sqm	1	30.00	0.55		16.50		
180	210		Sqm	1	30.00	0.55		16.50		
210	228		Sqm	1	18.00	0.55		9.90		
		2nd cross (upto jeeva nadi villas)								
		left side								
0	30		Sqm	1	30.00	0.45		13.50		
30	60		Sqm	1	30.00	0.45		13.50		
60	90		Sqm	1	30.00	0.45		13.50		
90	120		Sqm	1	30.00	0.45		13.50		
120	150		Sqm	1	30.00	0.45		13.50		
150	180		Sqm	1	30.00	0.45		13.50		
180	210		Sqm	1	30.00	0.45		13.50		
210	240		Sqm	1	30.00	0.45		13.50		

Scanned by CamScanner

1	15.00	4.65		69.75	
1	15.00	4.70		70.50	
1	15.00	4.40		66.00	
1	15.00	4.15		62.25	
1	15.00	4.25		63.75	
1	15.00	3.85		57.75	
1	15.00	3.85		57.75	
1	16.00	4.60		73.60	
1	16.30	4.30		70.09	
1	15.00	4.30		64.50	
1	15.00	4.15		62.25	
1	15.00	4.05		60.75	
1	15.00	4.45		66.75	
1	15.00	4.30		64.50	
1	15.00	4.10		61.50	
1	15.00	3.95		59.25	
1	15.00	4.40		66.00	
1	15.00	5.60		84.00	
1	15.00	5.60		84.00	
1	15.00	5.43		81.50	
1	15.00	5.20		78.00	
1	15.00	5.50		82.50	
1	15.00	5.30		79.50	
1	18.00	5.65		101.70	

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
45	55		Sqm	1	10.00	1.30		13.00		
60	65.1		Sqm	1	5.30	1.10		5.83		
70	75.3		Sqm	1	5.30	1.10		5.83		
		3'B cross								
0	30		Sqm	1	30.00	5		150.00		
30	60		Sqm	1	30.00	4.85		145.50		
60	90		Sqm	1	30.00	4.75		142.50		
90	126		Sqm	1	36.00	4.65		167.40		
		Opposite to 3rd B cross								
0	30		Sqm	1	30.00	5.6		168.00		
30	42.7		Sqm	1	12.70	5.4		68.58		
		3rd C cross road								
0	44.9		Sqm	1	44.90	5		224.50		
		Opposite to 3rd C cross								
0	30		Sqm	1	30.00	5.50		165.00		
30	60		Sqm	1	30.00	4.35		130.50		
60	90		Sqm	1	30.00	4.25		127.50		
90	120		Sqm	1	30.00	4.50		135.00		
120	136		Sqm	1	16.30	4.30		70.09		
		UAS appartment								
0	30		Sqm	1	30.00	4.50		135.00		
		3rd D cross road								
0	4		Sqm	1	4.00	5.00		20.00		
4.7	10		Sqm	1	5.30	4.95		26.24		
20	25.3		Sqm	1	5.30	4.95		26.24		
35	39		Sqm	1	4.00	4.95		19.80		
		3'A cross								
10	15.3		Sqm	1	5.30	0.9		4.77		
24.7	30		Sqm	1	5.30	0.9		4.77		
		JNANESHWARI LAYOUT								
		1st Cross Road								
0	30		Sqm	1	30.00	4.70		141.00		
30	58.1		Sqm	1	28.10	5.10		143.31		
		2nd Cross Road								
0	30		Sqm	1	30.00	4.70		141.00		
30	65.2		Sqm	1	35.20	4.70		165.44		
		3rd Cross Road								
0	30		Sqm	1	30.00	4.95		148.50		
30	67.6		Sqm	1	37.60	4.70		176.72		
		Kempegowda nagara main road								
0	15		sqm	1	15.00	5.55		83.25		
15	30		sqm	1	15.00	5.55		83.25		
30	45		sqm	1	15.00	5.50		82.50		
45	60		sqm	1	15.00	5.45		81.75		
60	75		sqm	1	15.00	5.40		81.00		
75	90		sqm	1	15.00	5.50		82.50		
90	105		sqm	1	15.00	5.25		78.75		
105	120		sqm	1	15.00	5.20		78.00		
120	135		sqm	1	15.00	5.80		87.00		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
		1st Block 13th Main Road								
		Left Side								
0	15		Sqm	1	15.00	0.55		8.25		
15	30		Sqm	1	15.00	0.55		8.25		
30	45		Sqm	1	15.00	0.55		8.25		
45	60		Sqm	1	15.00	0.55		8.25		
60	75		Sqm	1	15.00	0.55		8.25		
75	90		Sqm	1	15.00	0.55		8.25		
90	105		Sqm	1	15.00	0.55		8.25		
105	120		Sqm	1	15.00	0.55		8.25		
120	135		Sqm	1	15.00	0.55		8.25		
135	150		Sqm	1	15.00	0.55		8.25		
150	165		Sqm	1	15.00	0.55		8.25		
165	180		Sqm	1	15.00	0.55		8.25		
180	187		Sqm	1	7.20	0.55		3.96		
		Right Side								
0	15		Sqm	1	15.00	0.60		9.00		
15	30		Sqm	1	15.00	0.60		9.00		
30	45		Sqm	1	15.00	0.60		9.00		
45	60		Sqm	1	15.00	0.60		9.00		
60	75		Sqm	1	15.00	0.60		9.00		
75	90		Sqm	1	15.00	0.60		9.00		
90	105		Sqm	1	15.00	0.60		9.00		
105	120		Sqm	1	15.00	0.60		9.00		
120	135		Sqm	1	15.00	0.60		9.00		
135	150		Sqm	1	15.00	0.60		9.00		
150	165		Sqm	1	15.00	0.60		9.00		
165	180		Sqm	1	15.00	0.60		9.00		
180	187		Sqm	1	7.20	0.60		4.32		
		1st Block 14th Main Road								
		Left Side								
0	15		Sqm	1	15.00	0.60		9.00		
15	30		Sqm	1	15.00	0.60		9.00		
30	45		Sqm	1	15.00	0.60		9.00		
45	60		Sqm	1	15.00	0.60		9.00		
60	75		Sqm	1	15.00	0.60		9.00		
75	90		Sqm	1	15.00	0.60		9.00		
90	105		Sqm	1	15.00	0.60		9.00		
105	120		Sqm	1	15.00	0.60		9.00		
120	135		Sqm	1	15.00	0.60		9.00		
135	139		Sqm	1	4.10	0.60		2.46		
		Right Side								
0	15		Sqm	1	15.00	0.60		9.00		
15	30		Sqm	1	15.00	0.60		9.00		
30	45		Sqm	1	15.00	0.60		9.00		
45	60		Sqm	1	15.00	0.60		9.00		
60	75		Sqm	1	15.00	0.60		9.00		
75	90		Sqm	1	15.00	0.60		9.00		
90	105		Sqm	1	15.00	0.60		9.00		
105	120		Sqm	1	15.00	0.60		9.00		
120	135		Sqm	1	15.00	0.60		9.00		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
120	150		Sqm	1	30.00	0.60		18.00		
150	161		Sqm	1	11.30	0.60		6.78		
		Right side								
0	30		Sqm	1	30.00	0.65		19.50		
30	60		Sqm	1	30.00	0.65		19.50		
60	90		Sqm	1	30.00	0.65		19.50		
90	120		Sqm	1	30.00	0.65		19.50		
120	150		Sqm	1	30.00	0.65		19.50		
150	161		Sqm	1	11.30	0.65		7.35		
		2nd cross road								
0	30		Sqm	1	30.00	0.70		21.00		
30	60		Sqm	1	30.00	0.70		21.00		
60	90		Sqm	1	30.00	0.70		21.00		
90	120		Sqm	1	30.00	0.70		21.00		
120	150		Sqm	1	30.00	0.70		21.00		
150	162		Sqm	1	12.00	0.70		8.40		
		5th cross (DV Gundappa road)								
0	30		Sqm	1	30.00	0.90		27.00		
30	60		Sqm	1	30.00	0.90		27.00		
60	90		Sqm	1	30.00	0.90		27.00		
90	120		Sqm	1	30.00	0.90		27.00		
120	150		Sqm	1	30.00	0.90		27.00		
		CHIKKA VENKATAPPA LAYOUT								
		1sr cross road								
0	15		sqm	1	15.00	5.15		77.25		
15	30		sqm	1	15.00	5.00		75.00		
30	45		sqm	1	15.00	5.20		78.00		
45	60		sqm	1	15.00	5.25		78.75		
60	75		sqm	1	15.00	5.90		88.50		
75	95		sqm	1	20.00	6.10		122.00		
		2nd cross road								
0	15		sqm	1	15.00	4.95		74.25		
15	30		sqm	1	15.00	4.90		73.50		
30	45		sqm	1	15.00	5.00		75.00		
45	60		sqm	1	15.00	4.90		73.50		
60	75		sqm	1	15.00	4.75		71.25		
75	90		sqm	1	15.00	4.75		71.25		
		3rd cross road								
0	15		sqm	1	15.00	6.00		90.00		
15	30		sqm	1	15.00	5.50		82.50		
30	45		sqm	1	15.00	5.00		75.00		
45	60		sqm	1	15.00	4.70		70.50		
60	79		sqm	1	19.00	4.95		94.05		
		Chikka venkatappa Main Road								
0	15		sqm	1	15.00	4.60		69.00		
15	30		sqm	1	15.00	4.50		67.50		
30	45		sqm	1	15.00	4.30		64.50		
45	60		sqm	1	15.00	3.90		58.50		
60	75		sqm	1	15.00	4.15		62.25		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
15	30		Cum	1	15.00	4.70	0.05	3.53		
30	45		Cum	1	15.00	4.40	0.05	3.30		
45	60		Cum	1	15.00	4.15	0.05	3.11		
60	75		Cum	1	15.00	4.25	0.05	3.19		
75	90		Cum	1	15.00	3.85	0.05	2.89		
90	105		Cum	1	15.00	3.85	0.05	2.89		
105	121		Cum	1	16.00	4.60	0.05	3.68		
120	136		Cum	1	16.30	4.30	0.05	3.50		
		1st Main road								
0	15		Cum	1	15.00	4.30	0.05	3.23		
15	30		Cum	1	15.00	4.15	0.05	3.11		
30	45		Cum	1	15.00	4.05	0.05	3.04		
45	60		Cum	1	15.00	4.45	0.05	3.34		
60	75		Cum	1	15.00	4.30	0.05	3.23		
75	90		Cum	1	15.00	4.10	0.05	3.08		
90	105		Cum	1	15.00	3.95	0.05	2.96		
105	120		Cum	1	15.00	4.40	0.05	3.30		
120	135		Cum	1	15.00	5.60	0.05	4.20		
135	150		Cum	1	15.00	5.60	0.05	4.20		
150	165		Cum	1	15.00	5.10	0.05	3.83		
165	180		Cum	1	15.00	5.20	0.05	3.90		
180	195		Cum	1	15.00	5.50	0.05	4.13		
195	210		Cum	1	15.00	5.30	0.05	3.98		
210	228		Cum	1	18.00	5.65	0.05	5.09		
		Sidlingeshwara layout, Thindlu								
0	15		Cum	1	15.00	4.70	0.05	3.53		
15	30		Cum	1	15.00	4.85	0.05	3.64		
30	45		Cum	1	15.00	4.55	0.05	3.41		
45	60		Cum	1	15.00	4.20	0.05	3.15		
60	75		Cum	1	15.00	4.25	0.05	3.19		
75	90		Cum	1	15.00	4.05	0.05	3.04		
90	105		Cum	1	15.00	3.90	0.05	2.93		
105	120		Cum	1	15.00	3.90	0.05	2.93		
120	135		Cum	1	15.00	3.95	0.05	2.96		
135	155		Cum	1	20.00	4.05	0.05	4.05		
		Gowdru Beedi thindlu								
0	15		Cum	1	15.00	4.90	0.05	3.68		
15	30		Cum	1	15.00	4.55	0.05	3.41		
30	45		Cum	1	15.00	4.75	0.05	3.56		
45	62		Cum	1	17.00	7.15	0.05	6.08		
		BASAVA SAMITHI LAYOUT								
		6th cross								
		Left side								
0	15		Cum	1	15.00	1.30	0.05	0.98		
15	30		Cum	1	15.00	1.30	0.05	0.98		
30	45		Cum	1	15.00	1.30	0.05	0.98		
45	55		Cum	1	10.00	1.30	0.05	0.65		
60	65.3		Cum	1	5.30	1.10	0.05	0.29		
70	75.3		Cum	1	5.30	1.10	0.05	0.29		
		3'B cross								

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
0	15		Cum	1	15.00	0.55	0.05	0.41		
15	30		Cum	1	15.00	0.55	0.05	0.41		
30	45		Cum	1	15.00	0.55	0.05	0.41		
45	60		Cum	1	15.00	0.55	0.05	0.41		
60	75		Cum	1	15.00	0.55	0.05	0.41		
75	90		Cum	1	15.00	0.55	0.05	0.41		
90	105		Cum	1	15.00	0.55	0.05	0.41		
105	120		Cum	1	15.00	0.55	0.05	0.41		
120	135		Cum	1	15.00	0.55	0.05	0.41		
135	150		Cum	1	15.00	0.55	0.05	0.41		
150	165		Cum	1	15.00	0.55	0.05	0.41		
165	180		Cum	1	15.00	0.55	0.05	0.41		
180	187		Cum	1	7.20	0.55	0.05	0.20		
		Right Side								
0	15		Cum	1	15.00	0.60	0.05	0.45		
15	30		Cum	1	15.00	0.60	0.05	0.45		
30	45		Cum	1	15.00	0.60	0.05	0.45		
45	60		Cum	1	15.00	0.60	0.05	0.45		
60	75		Cum	1	15.00	0.60	0.05	0.45		
75	90		Cum	1	15.00	0.60	0.05	0.45		
90	105		Cum	1	15.00	0.60	0.05	0.45		
105	120		Cum	1	15.00	0.60	0.05	0.45		
120	135		Cum	1	15.00	0.60	0.05	0.45		
135	150		Cum	1	15.00	0.60	0.05	0.45		
150	165		Cum	1	15.00	0.60	0.05	0.45		
165	180		Cum	1	15.00	0.60	0.05	0.45		
180	187		Cum	1	7.20	0.60	0.05	0.22		
		1st Block 14th Main Road								
		Left Side								
0	15		Cum	1	15.00	0.60	0.05	0.45		
15	30		Cum	1	15.00	0.60	0.05	0.45		
30	45		Cum	1	15.00	0.60	0.05	0.45		
45	60		Cum	1	15.00	0.60	0.05	0.45		
60	75		Cum	1	15.00	0.60	0.05	0.45		
75	90		Cum	1	15.00	0.60	0.05	0.45		
90	105		Cum	1	15.00	0.60	0.05	0.45		
105	120		Cum	1	15.00	0.60	0.05	0.45		
120	135		Cum	1	15.00	0.60	0.05	0.45		
135	139		Cum	1	4.10	0.60	0.05	0.12		
		Right Side								
0	15		Cum	1	15.00	0.60	0.05	0.45		
15	30		Cum	1	15.00	0.60	0.05	0.45		
30	45		Cum	1	15.00	0.60	0.05	0.45		
45	60		Cum	1	15.00	0.60	0.05	0.45		
60	75		Cum	1	15.00	0.60	0.05	0.45		
75	90		Cum	1	15.00	0.60	0.05	0.45		
90	105		Cum	1	15.00	0.60	0.05	0.45		
105	120		Cum	1	15.00	0.60	0.05	0.45		
120	135		Cum	1	15.00	0.60	0.05	0.45		
135	139		Cum	1	4.10	0.60	0.05	0.45		
		2nd Block 13th Main Road						0.12		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
75	90		Cum	1	15.00	0.55	0.05	0.41		
90	105		Cum	1	15.00	0.55	0.05	0.41		
105	120		Cum	1	15.00	0.55	0.05	0.41		
120	135		Cum	1	15.00	0.55	0.05	0.41		
135	150		Cum	1	15.00	0.55	0.05	0.41		
150	165		Cum	1	15.00	0.55	0.05	0.41		
165	180		Cum	1	15.00	0.55	0.05	0.41		
180	193		Cum	1	12.60	0.55	0.05	0.35		
		3rd Block 8th Cross Road								
		Left Side								
0	15		Cum	1	15.00	0.55	0.05	0.41		
15	30		Cum	1	15.00	0.55	0.05	0.41		
30	45		Cum	1	15.00	0.55	0.05	0.41		
45	60		Cum	1	15.00	0.55	0.05	0.41		
60	75		Cum	1	15.00	0.55	0.05	0.41		
75	90		Cum	1	15.00	0.55	0.05	0.41		
90	105		Cum	1	15.00	0.55	0.05	0.41		
105	120		Cum	1	15.00	0.55	0.05	0.41		
120	135		Cum	1	15.00	0.55	0.05	0.41		
135	150		Cum	1	15.00	0.55	0.05	0.41		
150	165		Cum	1	15.00	0.55	0.05	0.41		
165	180		Cum	1	15.00	0.55	0.05	0.41		
180	185		Cum	1	5.00	0.55	0.05	0.14		
		Right Side								
0	15		Cum	1	15.00	0.60	0.05	0.45		
15	30		Cum	1	15.00	0.60	0.05	0.45		
30	45		Cum	1	15.00	0.60	0.05	0.45		
45	60		Cum	1	15.00	0.60	0.05	0.45		
60	75		Cum	1	15.00	0.60	0.05	0.45		
75	90		Cum	1	15.00	0.60	0.05	0.45		
90	105		Cum	1	15.00	0.60	0.05	0.45		
105	120		Cum	1	15.00	0.60	0.05	0.45		
120	135		Cum	1	15.00	0.60	0.05	0.45		
135	150		Cum	1	15.00	0.60	0.05	0.45		
150	165		Cum	1	15.00	0.60	0.05	0.45		
165	180		Cum	1	15.00	0.60	0.05	0.45		
180	185		Cum	1	5.00	0.60	0.05	0.15		
		GANESHA LAYOUT								
		Sri ram shrayas appartment, Telecom								
0	23		Cum	1	23.00	5.00	0.05	5.75		
		TELECOM LAYOUT								
		3rd cross road								
0	30		Cum	1	30.00	0.60	0.05	0.90		
30	60		Cum	1	30.00	0.60	0.05	0.90		
60	90		Cum	1	30.00	0.60	0.05	0.90		
90	120		Cum	1	30.00	0.60	0.05	0.90		
120	150		Cum	1	30.00	0.60	0.05	0.90		
150	161		Cum	1	11.30	0.60	0.05	0.34		
		Right side								

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
							Qty Above 125%	93.11	7618.42	709333.92
		Basic rate	6717							
		6% weightage	403.02							
		Total Rs.	7120.02							
		(+7%)TP	498.401							
		Net Total Rs.	**7618.42**							
Item no.17		Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatement including cost of all materials, labour, HOM of machineries complete as per specifications. and as per the directions of the Engineer-in-charge of the work .								
		Road Portion								
		Defence layout								
		1st main road								
0	15		Sqm	1	15.00	5.20		78.00		
15	30		Sqm	1	15.00	4.45		66.75		
30	45		Sqm	1	15.00	4.55		68.25		
45	60		Sqm	1	15.00	4.40		66.00		
60	75		Sqm	1	15.00	4.25		63.75		
75	90		Sqm	1	15.00	4.80		72.00		
90	106		Sqm	1	16.00	5.60		89.60		
		2nd Cross Road								
0	15		Sqm	1	15.00	5.25		78.75		
15	30		Sqm	1	15.00	4.75		71.25		
30	45		Sqm	1	15.00	4.90		73.50		
45	60		Sqm	1	15.00	4.85		72.75		
60	75		Sqm	1	15.00	4.35		65.25		
75	90		Sqm	1	15.00	4.25		63.75		
90	105		Sqm	1	15.00	4.50		67.50		
105	120		Sqm	1	15.00	4.60		69.00		
120	132.2		Sqm	1	12.20	5.00		61.00		
		3rd cross road								
0	15		Sqm	1	15.00	5.15		77.25		
15	30		Sqm	1	15.00	3.75		56.25		
30	45		Sqm	1	15.00	4.15		62.25		
45	60		Sqm	1	15.00	4.45		66.75		
60	75		Sqm	1	15.00	4.50		67.50		
75	90		Sqm	1	15.00	4.70		70.50		
90	105		Sqm	1	15.00	4.70		70.50		
105	120		Sqm	1	15.00	4.65		69.75		
120	135		Sqm	1	15.00	4.65		69.75		
135	150		Sqm	1	15.00	4.75		71.25		
150	157		Sqm	1	7.00	5.15		36.05		
		7th main road								
0	15		Sqm	1	15.00	6.50		97.50		
15	30		Sqm	1	15.00	4.80		72.00		
30	45		Sqm	1	15.00	4.80		72.00		
45	60		Sqm	1	15.00	4.80		72.00		
60	75		Sqm	1	15.00	4.65		69.75		
75	90		Sqm	1	15.00	4.50		67.50		
90	105		Sqm	1	15.00	4.65		69.75		
105	120		Sqm	1	15.00	5.05		75.75		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
178	193		Sqm	1	15.00	5.75		86.25		
193	207		Sqm	1	14.00	6.40		89.60		
		1st A in 20th A main CQAL lyt								
0	15		Sqm	1	15.00	6.00		90.00		
15	30		Sqm	1	15.00	5.95		89.25		
30	45		Sqm	1	15.00	5.80		87.00		
		1st B in 20th A main CQAL lyt						0.00		
0	15		Sqm	1	15.00	5.70		85.50		
15	30		Sqm	1	15.00	5.70		85.50		
30	47		Sqm	1	17.00	5.65		96.05		
		20th E cross road, 1st main								
0	15		Sqm	1	15.00	5.30		79.50		
15	30		Sqm	1	15.00	5.85		87.75		
30	48		Sqm	1	18.00	5.50		99.00		
		3rd main C block								
0	15		Sqm	1	15.00	5.30		79.50		
15	30		Sqm	1	15.00	5.75		86.25		
30	45		Sqm	1	15.00	6.05		90.75		
45	60		Sqm	1	15.00	6.25		93.75		
60	75		Sqm	1	15.00	6.50		97.50		
75	90		Sqm	1	15.00	6.35		95.25		
90	105		Sqm	1	15.00	6.05		90.75		
105	120		Sqm	1	15.00	5.90		88.50		
120	130		Sqm	1	10.00	5.75		57.50		
		6th main								
0	15		Sqm	1	15.00	6.20		93.00		
15	30		Sqm	1	15.00	6.40		96.00		
30	45		Sqm	1	15.00	6.30		94.50		
45	60		Sqm	1	15.00	6.10		91.50		
60	75		Sqm	1	15	6.35		95.25		
75	90		Sqm	1	15.00	6.55		98.25		
90	105		Sqm	1	15.00	6.55		98.25		
105	109		Sqm	1	4.00	7.05		28.20		
		5th main								
0	15		Sqm	1	15.00	6.80		102.00		
15	30		Sqm	1	15.00	6.90		103.50		
30	45		Sqm	1	15.00	7.05		105.75		
45	60		Sqm	1	15.00	6.75		101.25		
60	75		Sqm	1	15.00	6.65		99.75		
75	90		Sqm	1	15.00	7.05		105.75		
90	105		Sqm	1	15.00	6.95		104.25		
105	120		Sqm	1	15.00	6.55		98.25		
120	134.7		Sqm	1	14.70	7.20		105.84		
		20th D cross, 1st main								
0	15		Sqm	1	15.00	8.10		121.50		
15	30		Sqm	1	15.00	8.15		122.25		
30	45		Sqm	1	15.00	8.05		120.75		
45	60		Sqm	1	15.00	7.75		116.25		
60	75		Sqm	1	15.00	8.00		120.00		
75	90		Sqm	1	15.00	8.15		122.25		
90	105		Sqm	1	15.00	7.35		110.25		
105	118		Sqm	1	13.00	4.95		64.35		
		1st main road Govt School road								
0	30		Sqm	1	30.00	4.75		142.50		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
30	60		Sqm	1	30.00	4.95		148.50		
60	90		Sqm	1	30.00	5.25		157.50		
90	120		Sqm	1	30.00	5.50		165.00		
120	150		Sqm	1	30.00	5.50		165.00		
150	180		Sqm	1	30.00	4.80		144.00		
180	192.7		Sqm	1	12.70	4.75		60.32		
		Maruthinagar								
		9th B cross road maruthi nagara								
0	15		Sqm	1	15.00	6.05		90.75		
15	30		Sqm	1	15.00	5.25		78.75		
30	45		Sqm	1	15.00	4.65		69.75		
45	60		Sqm	1	15.00	4.65		69.75		
60	75		Sqm	1	15.00	5.25		78.75		
75	90		Sqm	1	15.00	5.25		78.75		
90	105		Sqm	1	15.00	4.95		74.25		
105	115		Sqm	1	10.00	5.00		50.00		
		11th cross maruthi nagara								
0	15		Sqm	1	15.00	4.55		68.25		
15	30		Sqm	1	15.00	4.05		60.75		
30	45		Sqm	1	15.00	4.45		66.75		
45	60		Sqm	1	15.00	4.95		74.25		
60	71		Sqm	1	11.00	5.15		56.65		
		3rd cross Devinagar								
0	15		Sqm	1	15.00	3.70		55.50		
15	30		Sqm	1	15.00	3.35		50.25		
30	45		Sqm	1	15.00	3.40		51.00		
45	60		Sqm	1	15.00	3.45		51.75		
60	75		Sqm	1	15.00	3.50		52.50		
75	90		Sqm	1	15.00	3.60		54.00		
90	107		Sqm	1	17.00	3.80		64.60		
		Hanumaiah Layout Main Road								
0	30		Sqm	1	30.00	4.55		136.50		
30	60		Sqm	1	30.00	5.25		157.50		
60	90		Sqm	1	30.00	5.60		168.00		
90	120		Sqm	1	30.00	5.90		177.00		
120	150		Sqm	1	30.00	5.65		169.50		
150	180		Sqm	1	30.00	5.80		174.00		
180	210		Sqm	1	30.00	6.55		196.50		
210	240		Sqm	1	30.00	6.90		207.00		
240	270		Sqm	1	30.00	7.10		213.00		
270	300		Sqm	1	30.00	6.60		198.00		
300	330		Sqm	1	30.00	6.55		196.50		
330	360		Sqm	1	30.00	6.95		208.50		
360	390		Sqm	1	30.00	6.90		207.00		
390	420		Sqm	1	30.00	6.60		198.00		
420	450		Sqm	1	30.00	6.50		195.00		
450	480		Sqm	1	30.00	6.90		207.00		
480	510		Sqm	1	30.00	6.65		199.50		
510	515		Sqm	1	5.30	6.30		33.39		
		1st Cross Tata Nagar(BESCOM Office Loop Road)								

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
60	75		Sqm	1	15.00	8.60		129.00		
75	90		Sqm	1	15.00	8.95		134.25		
90	105		Sqm	1	15.00	8.90		133.50		
105	120		Sqm	1	15.00	8.35		125.25		
120	136		Sqm	1	16.30	8.15		132.85		
		Amco layout 1st main(impact college opp)								
0	6		Sqm	1	6.00	10.35		62.10		
6	10		Sqm	1	4.00	8.35		33.40		
10	25		Sqm	1	15.00	7.50		112.50		
25	40		Sqm	1	15.00	7.80		117.00		
40	55		Sqm	1	15.00	8.00		120.00		
55	70		Sqm	1	15.00	7.85		117.75		
70	85		Sqm	1	15.00	7.65		114.75		
85	100		Sqm	1	15.00	7.60		114.00		
100	115		Sqm	1	15.00	7.55		113.25		
115	130		Sqm	1	15.00	7.00		105.00		
130	145		Sqm	1	15.00	7.00		105.00		
145	150		Sqm	1	5.00	7.50		37.50		
		Tata Nagar								
		5th Cross	Sqm	1	307.00	7.00		2149.00		
		3rd main Road	Sqm	1	139.00	6.80		945.20		
							Sub Total	28802.47		
		Deduct prime coat						-2217.68		
							Sub total	26584.79		
		VIRUPAKSHAPURA								
		1st cross (pole factory road)								
0	30		Sqm	1	30.00	6.05		181.50		
30	60		Sqm	1	30.00	4.95		148.50		
60	90		Sqm	1	30.00	5.23		156.75		
90	120		Sqm	1	30.00	5.33		159.75		
120	150		Sqm	1	30.00	5.18		155.25		
150	180		Sqm	1	30.00	5.43		162.75		
180	210		Sqm	1	30.00	5.45		163.50		
210	228		Sqm	1	18.00	5.18		93.15		
		2nd cross (upto jeeva nadi villas)								
0	30		Sqm	1	30.00	5.20		156.00		
30	60		Sqm	1	30.00	5.10		153.00		
60	90		Sqm	1	30.00	4.95		148.50		
90	120		Sqm	1	30.00	4.90		147.00		
120	150		Sqm	1	30.00	4.80		144.00		
150	180		Sqm	1	30.00	4.55		136.50		
180	210		Sqm	1	30.00	4.70		141.00		
210	240		Sqm	1	30.00	4.95		148.50		
240	270		Sqm	1	30.00	5.15		154.50		
270	297		Sqm	1	27.00	5.85		157.95		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
30	65.2		Sqm	1	35.20	4.70		165.44		
		3Rd cross road								
0	30		Sqm	1	30.00	5.40		162.00		
30	67.6		Sqm	1	37.60	4.75		178.60		
		SIR M.V LAYOUT								
		2nd main road(ganesh temple road or gas godown)								
0	30		Sqm	1	30.00	5.25		157.50		
30	60		Sqm	1	30.00	5.20		156.00		
60	90		Sqm	1	30.00	5.05		151.50		
90	120		Sqm	1	30.00	5.35		160.50		
120	150		Sqm	1	30.00	6.05		181.50		
150	180		Sqm	1	30.00	6.40		192.00		
180	210		Sqm	1	30.00	6.15		184.50		
210	240		Sqm	1	30.00	6.40		192.00		
240	270		Sqm	1	30.00	6.95		208.50		
270	300		Sqm	1	30.00	6.65		199.50		
300	330		Sqm	1	30.00	6.25		187.50		
330	360		Sqm	1	30.00	6.10		183.00		
360	396		Sqm	1	36.00	6.35		228.60		
		13th cross (upto 5th main ananda layout)								
0	30		Sqm	1	30.00	4.75		142.50		
30	60		Sqm	1	30.00	5.10		153.00		
60	90		Sqm	1	30.00	5.00		150.00		
90	120		Sqm	1	30.00	4.80		144.00		
120	150		Sqm	1	30.00	5.05		151.50		
150	180		Sqm	1	30.00	5.45		163.50		
180	210		Sqm	1	30.00	5.45		163.50		
210	240		Sqm	1	30.00	5.40		162.00		
240	270		Sqm	1	30.00	5.05		151.50		
270	300		Sqm	1	30.00	4.75		142.50		
300	327		Sqm	1	26.90	5.10		137.19		
		cross road								
0	30		Sqm	1	30.00	4.95		148.50		
30	53.2		Sqm	1	23.20	5.45		126.44		
		11th A cross road								
0	30		Sqm	1	30.00	4.95		148.50		
30	60		Sqm	1	30.00	4.70		141.00		
60	81.8		Sqm	1	21.80	4.50		98.10		
		12th cross road								
0	30		Sqm	1	30.00	5.35		160.50		
30	60		Sqm	1	30.00	4.55		136.50		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
15	30		Sqm	1	15.00	4.90		73.50		
30	45		Sqm	1	15.00	4.90		73.50		
45	60		Sqm	1	15.00	4.95		74.25		
60	75		Sqm	1	15.00	5.00		75.00		
75	90		Sqm	1	15.00	4.95		74.25		
90	105		Sqm	1	15.00	4.90		73.50		
105	120		Sqm	1	15.00	4.85		72.75		
120	135		Sqm	1	15.00	4.90		73.50		
135	150		Sqm	1	15.00	4.95		74.25		
150	165		Sqm	1	15.00	4.90		73.50		
165	180		Sqm	1	15.00	4.90		73.50		
180	194		Sqm	1	13.70	5.45		74.66		
		1st Cross Road								
0	15		Sqm	1	15.00	6.05		90.75		
15	30		Sqm	1	15.00	4.80		72.00		
30	45		Sqm	1	15.00	4.55		68.25		
45	60		Sqm	1	15.00	4.45		66.75		
60	75		Sqm	1	15.00	4.45		66.75		
75	90		Sqm	1	15.00	4.50		67.50		
90	105		Sqm	1	15.00	4.70		70.50		
105	120		Sqm	1	15.00	4.70		70.50		
120	134		Sqm	1	13.90	5.90		82.01		
		GURUDARSHAN LAYOUT								
		5th Cross Road								
0	30		Sqm	1	30.00	4.50		135.00		
30	60		Sqm	1	30.00	4.70		141.00		
60	90		Sqm	1	30.00	4.85		145.50		
90	105		Sqm	1	14.80	4.80		71.04		
		6th Cross Road								
0	30		Sqm	1	30.00	4.80		144.00		
30	60		Sqm	1	30.00	4.90		147.00		
60	90		Sqm	1	30.00	4.85		145.50		
90	104		Sqm	1	14.30	4.85		69.36		
		7th Cross Road								
0	30		Sqm	1	30.00	4.80		144.00		
30	60		Sqm	1	30.00	4.15		124.50		
60	90		Sqm	1	30.00	4.20		126.00		
90	105		Sqm	1	14.50	4.80		69.60		
		Kempegowda nagara main road								
0	15		sqm	1	15.00	5.55		83.25		
15	30		sqm	1	15.00	5.55		83.25		
30	45		sqm	1	15.00	5.50		82.50		
45	60		sqm	1	15.00	5.45		81.75		
60	75		sqm	1	15.00	5.40		81.00		
75	90		sqm	1	15.00	5.50		82.50		
90	105		sqm	1	15.00	5.25		78.75		
105	120		sqm	1	15.00	5.20		78.00		
120	135		sqm	1	15.00	5.80		87.00		
135	150		sqm	1	15.00	5.85		87.75		
150	171		sqm	1	21.00	5.90		123.90		
171	186		sqm	1	15.00	6.20		93.00		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
0	30		Sqm	1	30.00	4.55		136.50		
30	60		Sqm	1	30.00	4.65		139.50		
60	99.2		Sqm	1	39.20	4.55		178.36		
		CHIKKA VENKATAPPA LAYOUT								
		1sr cross road								
0	15		sqm	1	15.00	5.15		77.25		
15	30		sqm	1	15.00	5.00		75.00		
30	45		sqm	1	15.00	5.20		78.00		
45	60		sqm	1	15.00	5.25		78.75		
60	75		sqm	1	15.00	5.90		88.50		
75	95		sqm	1	20.00	6.10		122.00		
		2nd cross road								
0	15		sqm	1	15.00	4.95		74.25		
15	30		sqm	1	15.00	4.90		73.50		
30	45		sqm	1	15.00	5.00		75.00		
45	60		sqm	1	15.00	4.90		73.50		
60	75		sqm	1	15.00	4.75		71.25		
75	90		sqm	1	15.00	4.75		71.25		
		3rd cross road								
0	15		sqm	1	15.00	6.00		90.00		
15	30		sqm	1	15.00	5.50		82.50		
30	45		sqm	1	15.00	5.00		75.00		
45	60		sqm	1	15.00	4.70		70.50		
60	79		sqm	1	19.00	4.95		94.05		
		Chikka venkatappa Main Road								
0	15		sqm	1	15.00	4.60		69.00		
15	30		sqm	1	15.00	4.50		67.50		
30	45		sqm	1	15.00	4.30		64.50		
45	60		sqm	1	15.00	3.90		58.50		
60	75		sqm	1	15.00	4.15		62.25		
75	90		sqm	1	15.00	5.15		77.25		
90	106		sqm	1	16.00	6.20		99.20		
106	120		sqm	1	14.00	5.65		79.10		
120	135		sqm	1	15.00	4.60		69.00		
135	150		sqm	1	15.00	4.40		66.00		
150	165		sqm	1	15.00	4.40		66.00		
165	180		sqm	1	15.00	4.50		67.50		
180	195		sqm	1	15.00	4.65		69.75		
195	210		sqm	1	15.00	4.70		70.50		
210	225		sqm	1	15.00	4.80		72.00		
		DESHBANDHU NAGAR								
		3rd Road								
0	15		sqm	1	15.00	6.30		94.50		
15	30		sqm	1	15.00	5.05		75.75		
30	45		sqm	1	15.00	4.45		66.75		
45	60		sqm	1	15.00	4.45		66.75		
60	75		sqm	1	15.00	4.95		74.25		
		5th cross RK Layourt								

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
150	165		Sqm	1	15.00	6.90		103.50		
165	180		Sqm	1	15.00	6.10		91.50		
180	195		Sqm	1	15.00	5.95		89.25		
195	210		Sqm	1	15.00	5.95		89.25		
210	217		Sqm	1	7	6		42		
		6th Cross								
0	15		Sqm	1	15.00	6.00		90.00		
15	30		Sqm	1	15.00	5.90		88.50		
30	45		Sqm	1	15.00	6.65		99.75		
45	60		Sqm	1	15.00	6.55		98.25		
60	75		Sqm	1	15.00	6.00		90.00		
75	90		Sqm	1	15.00	6.05		90.75		
90	104		Sqm	1	14.00	6.70		93.80		
		5th cross road								
0	15		Sqm	1	15.00	8.25		123.75		
15	30		Sqm	1	15.00	7.80		117.00		
30	45		Sqm	1	15.00	7.40		111.00		
45	60		Sqm	1	15.00	7.25		108.75		
60	75		Sqm	1	15.00	7.60		114.00		
75	90		Sqm	1	15.00	7.95		119.25		
90	105		Sqm	1	15.00	8.10		121.50		
105	120		Sqm	1	15.00	8.30		124.50		
120	135		Sqm	1	15.00	8.30		124.50		
135	139.4		Sqm	1	4.40	8.75		38.50		
		CQAL Layout								
		20th B Cross Rd (8th Mn to Kodigehalli Mn Rd)								
		CQAL Layout	Sqm	1						
0	15		Sqm	1	15.00	5.40		81.00		
15	22		Sqm	1	7.00	5.40		37.80		
0	15		Sqm	1	15.00	8.65		129.75		
15	30		Sqm	1	15.00	7.15		107.25		
30	45		Sqm	1	15.00	7.25		108.75		
45	60		Sqm	1	15.00	7.25		108.75		
60	75		Sqm	1	15.00	7.15		107.25		
75	90		Sqm	1	15.00	7.15		107.25		
90	105		Sqm	1	15.00	6.95		104.25		
105	120		Sqm	1	15.00	6.95		104.25		
120	135		Sqm	1	15.00	7.00		105.00		
135	150		Sqm	1	15.00	7.00		105.00		
150	165		Sqm	1	15.00	7.10		106.50		
165	180		Sqm	1	15.00	7.20		108.00		
180	195		Sqm	1	15.00	8.10		121.50		
195	210		Sqm	1	15.00	7.95		119.25		
210	225		Sqm	1	15.00	7.05		105.75		
225	240		Sqm	1	15.00	6.85		102.75		
240	255		Sqm	1	15.00	6.30		94.50		
255	270		Sqm	1	15.00	6.20		93.00		
270	285		Sqm	1	15.00	6.20		93.00		
285	305.7		Sqm	1	20.70	6.90		142.83		
		20thC (7th main to 2nd main road-hello kids)								

Scanned by CamScanner

BBMP (ward No,08 And 09)

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
30	45		Sqm	1	15.00	6.30		94.50		
45	60		Sqm	1	15.00	6.10		91.50		
60	75		Sqm	1	15	6.35		95.25		
75	90		Sqm	1	15.00	6.55		98.25		
90	105		Sqm	1	15.00	6.55		98.25		
105	109		Sqm	1	4.00	7.05		28.20		
		5th main								
0	15		Sqm	1	15.00	6.80		102.00		
15	30		Sqm	1	15.00	6.90		103.50		
30	45		Sqm	1	15.00	7.05		105.75		
45	60		Sqm	1	15.00	6.75		101.25		
60	75		Sqm	1	15.00	6.65		99.75		
75	90		Sqm	1	15.00	7.05		105.75		
90	105		Sqm	1	15.00	6.95		104.25		
105	120		Sqm	1	15.00	6.55		98.25		
120	134.7		Sqm	1	14.70	7.20		105.84		
		20th D cross, 1st main								
0	15		Sqm	1	15.00	8.10		121.50		
15	30		Sqm	1	15.00	8.15		122.25		
30	45		Sqm	1	15.00	8.05		120.75		
45	60		Sqm	1	15.00	7.75		116.25		
60	75		Sqm	1	15.00	8.00		120.00		
75	90		Sqm	1	15.00	8.15		122.25		
90	105		Sqm	1	15.00	7.35		110.25		
105	118		Sqm	1	13.00	4.95		64.35		
		1st main road Govt School road								
0	30		Sqm	1	30.00	4.75		142.50		
30	60		Sqm	1	30.00	4.95		148.50		
60	90		Sqm	1	30.00	5.25		157.50		
90	120		Sqm	1	30.00	5.50		165.00		
120	150		Sqm	1	30.00	5.50		165.00		
150	180		Sqm	1	30.00	4.80		144.00		
180	192.7		Sqm	1	12.70	4.75		60.32		
		Maruthinagar								
		5th A cross road								
0	15.5		Sqm	1	15.50	4.60		71.30		
		5th B cross								
0	20		Sqm	1	20.00	4.60		92.00		
		5th D cross								
0	15		Sqm	1	15.00	5.50		82.50		
15	25.5		Sqm	1	10.50	5.60		58.80		
		9th B cross road maruthi nagara								
0	15		Sqm	1	15.00	6.05		90.75		
15	30		Sqm	1	15.00	5.25		78.75		
30	45		Sqm	1	15.00	4.65		69.75		
45	60		Sqm	1	15.00	4.65		69.75		
60	75		Sqm	1	15.00	5.25		78.75		
75	90		Sqm	1	15.00	5.25		78.75		
90	105		Sqm	1	15.00	4.95		74.25		
105	115		Sqm	1	10.00	5.00		50.00		

Scanned by CamScanner